



# Mahesh Prefab Pvt Ltd

(Mfrs of Glass Fibre Reinforced Concrete)

Corporate Office: 38<sup>th</sup> Mile Stone, Delhi Jaipur Highway, NH – 8, Behrampur Road, Khandsa, Gurgaon – 122001, Haryana

Factory: A46 - A, RIICO Industrial Area, KHUSHKHERA - 301019, Bhiwadi, Rajasthan

## Process Flow Control Chart

Order/Work Order followed with instructions to the Plant Manager  
Creation of Job Card assigned to the client

Final, approved AutoCAD design of the GRC element to be made available for Pattern Making:

Pattern making in POP/Gypsum - For Client Approval

After client approval, actual mould making in rubber/FRP

Casting of the Approved GRC Element Mould;  
De-Moulding of the same from the cast  
Wet Curing of the Approved GRC Element (At least 7 days)

Final finishing, including touch up, if required  
Final Packing of the Approved GRC Element

Dispatch